

MDU Approved Meter Socket List May 2018 Ver 4u

			Amp	# of	Lever	Date
Manufacturer	Cat. #	Description	Rating	Terminals	Bypass	Add/Revise
Durham	D 1006034	Residential, OH, lay in	200	4	no	5/18
Eaton	E UTRS240ACH	Residential, UG, stud	200	4	no	3/14
Milbank	M U2986-O	Residential, UG, stud	200	4	no	3/14
Milbank	M U7040-XL-TG	Residential, OH, lay in	200	4	no	5/18
Siemens	S UAS278-PG	Residential, UG, stud	200	4	no	5/16
Durham	D UTH4330U	Residential/Commercial, OH/UG, stud	320	4	yes	3/14
Durham	D UTH5210B	Residential/Commercial, OH/UG, stud	200	4 or 5	yes	3/14
Milbank	M U4801-XL-5T9	Res/Com, OH, lay in	200	4 or 5	yes	5/18
Milbank	M U1129-O	Residential/Commercial, UG, stud	320	4	yes	5/18
Milbank	M U1252-X	Residential, OH/UG, stud, Duplex	200	4	no	5/18
Milbank	M U9865-R-RL	Residential/Commercial, OH/UG, stud	200	4	yes	3/14
Siemens	S 42507-025 (4 term)	Residential, OH, stud	200	4	yes	5/16
Siemens	S 9804-8946	Residential, OH/UG, lay in/stud	200	4	yes	5/16
Siemens	S UA2717-YG	Residential, OH/UG, lay in/stud	200	4	yes	5/16
Durham	D STS131C	Commercial, Instrument, w/ test plate	20	13	no	3/14
Durham	D STS61C	Commercial, Instrument, w/ test plate	20	6	no	3/14
Durham	D UTH7210T	Commercial, OH/UG, stud	200	7	yes	3/14
Durham	D UTH7330U	Commercial, OH/UG, stud	320	7	yes	3/14
Milbank	M U9761-R	Commercial, OH/UG, stud	200	7	yes	5/18
Milbank	M U2120-X	Commercial, UG, stud	320	7	yes	3/14
Milbank	M U2594-X	Commercial, OH/UG, stud	320	7	yes	5/18
Milbank	M U4911-X	Commercial, OH/UG, stud	320	7	yes	5/18
Milbank	M UC7444-XL	Commercial, Instrument, w/ test plate & closure plate	20	8	no	5/18
Milbank	M UC7445-XL	Commercial, Instrument, w/ test plate & closure plate	20	13	no	5/18
Milbank	M UC7478-XL	Commercial, Instrument, w/ test plate & closure plate	20	6	no	5/18
Siemens	S 42507-025 (7 term)	Commercial, OH, stud	200	7	yes	5/16
Siemens	S 44707-02	Commercial, OH/UG, stud	320	7	yes	5/16
Siemens	S 47604-02QG	Commercial, OH/UG, stud	320	4	yes	5/16
Siemens	S 47707-02	Commercial, OH, stud	320	7	yes	5/16
Siemens	S 48104-02	Commercial, OH/UG, stud	320	4	yes	5/16
Siemens	S 48707-02FE	Commercial, OH/UG, stud	320	7	yes	5/16
Siemens	S 49007-02	Commercial, OH/UG, stud	320	7	yes	5/16

MDU Approved Meter Socket List May 2018 Ver 4u

			Amp	# of	Lever	Date
Manufacturer	Cat. #	Description	Rating	Terminals	Bypass	Add/Revise
Siemens	S 9804-9026	Commercial, UG, stud	200	7	yes	3/14
Milbank	M U9647N-XL200-TG	Residential, OH, lay-in, 200A Break. with dual load lugs	200	4	no	3/14
Siemens	S MC****B1200RCT	Res/Com, OH/UG,stud/lay in, 200A Break w/ loadcenter	200	4	no	5/18
Siemens	S MC****B1400RLTM	Res/Com, OH/UG,stud/lay in, 200A Break w/ loadcenter	320	4	yes	5/18
Eaton	E CMBX****B200BTS	Res/Com, OH/UG, lay in, 200A Break w/ loadcenter	200	4 or 5	yes	5/18
Eaton	E MB****B200BTS	Res/Com, OH/UG, lay in, 200A Break w/ loadcenter	200	4	no	5/18
Milbank	M M5U5894-X-2-200	Res/Com, OH/UG, stud, two 200A Breakers	320	4	yes	3/14
Milbank	M U4282-XL-200	Residential, OH/UG, stud, 200A Breaker	200	4	no	3/14
Milbank	M U5059-X-2-200-K3L	Res/Com, OH/UG, stud/lay in, two 200A Breakers	320	4	yes	5/16
Square D	Q RC***D200CH	Res/Com, OH/UG, lay in, 200A Break w/ loadcenter	200	4	no	5/18
Midwest	MW R281C1P6H	Mobile Home Pedestal, lay in, two 200A Breakers	200	4	no	3/14
Milbank	M U5136	Mobile Home Pedestal, lay in, one 200A Breakers	200	4	no	5/16
Siemens	S MP****B1200R	Mobile Home Pedestal, lay in, one 200A Breakers	200	4	no	5/18

Notes:

* - this is part of the Cat. # that can vary depending on features

- first digit of Cat. # is manufacturer (M - Milbank, E - Eaton, D - Durham, S - Siemens, MW - Midwest, Q - Square D)